

## **ATTACHMENT A**

### **Project Scope of Work**

The project scope of work includes: vegetation removal; removal of existing fences; no climb fence fabrication and installation; man-gate installation at each property; and miscellaneous removals and disposal as shown on the plans in one geographic area as follows and as shown in Attachment E (Project Construction Drawings). Project areas require access through private property, and access must be coordinated with SBFCA. All work must be completed by November 15, 2022.

#### **Bid Schedule A**

The removal of all vegetation behind the proposed fence in the levee embankment, within the 20' encroachment area from the proposed fence, that is smaller than 4 inches in diameter, the trimming of trees that are larger than 4 inches in diameter, and the removal of miscellaneous materials that are in the levee embankment.

#### **Bid Schedule B**

Install 2,460 LF of a no climb fence without extension arms, 215 LF of a no climb fence with extension arms, 32 man-gates and removal and disposal of approximately 2,160 LF of existing fence. Fence posts shall be installed 8' on center following details A85 and UFC 702 on Sheet C-501 as shown in Attachment E.

#### **Alternative Bid Schedule C**

The removal of the existing wooden retaining wall, concrete stairs, and railing in the embankment of the levee. The rebuilding of the levee slope after the removal of these encroachments, importing type 1 levee fill for embankment, and hydroseeding the impacted area.

#### **Alternative Bid Schedule D**

The removal of the existing concrete retaining wall. The rebuilding of the levee slope after the removal of these encroachments, importing type 1 levee fill for embankment, and hydroseeding the impacted area.

## **Alternative Bid Schedule E**

The removal of the existing concrete retaining wall. The rebuilding of the levee slope after the removal of these encroachments, importing type 1 levee fill for embankment, and hydroseeding the impacted area.