

ATTACHMENT A
LEVEE DISTRICT 1 ACCESS CONTROL PROJECT

Project Scope of Work

The project scope of work includes: pipe gate and pipe fence fabrication and installation; installation of concrete barriers; miscellaneous removals and disposal as shown on the plans in two geographically separate project areas as follows and as shown in Attachment E (Project Construction Drawings). Project areas require access through private property, and access must be coordinated with SBFCA. All work must be completed by April 22, 2022.

Project Area 1 (Near the Feather Water District South Pond)

1. Install one pipe gate, install 5 LF of pipe fence, install 1286 LF of concrete barriers, and removal and disposal of approximately 15 LF of an existing gate. Concrete blocks shall be placed approximately 30-feet from the landside toe of the levee.

Project Area 2 (Lyon Avenue to north of Ashford Avenue)

1. Install one pipe gate, install 10 LF of pipe fence, and install approximately 5,483 LF of concrete block barrier. Concrete blocks shall be placed approximately 30-feet from the landside toe of the levee.